

Advertisement for bids
New York Ave. Underground Utility Work
City Project No. 314-21
City of Breckenridge
Feb, 05 2021

Attention Bidders:

Sealed bids will be received by the City of Breckenridge, Minnesota at the City Administrator's Office at 420 Nebraska Avenue, Breckenridge, MN 56520 until 1:00 PM on Friday, Feb, 26th and will be opened and publicly read by the representatives of the City, in the City Council Chambers at City Hall at an open meeting on the above date at 1:00 PM.

The project scope is burying electrical utilities along New York Ave. from 6th St. S. to 10th St S. (the "project"). Plans and specifications for the project are on file in the office of the City Administrator. Copies of the plans and specifications will be furnished on request to any prospective bidder.

All bids must be sealed and clearly labeled as: City Project No. 314-21

The work to be completed on the project will primarily consist of directional boring and pulling in innerduct. The linear footage required to be bored will be approximately 4,500 ft. The innerduct to be pulled in will be approximately 14,600 linear ft. **Staking sheets will be sent electronically to any bidder upon request.**

The competent/qualified contractor will be required to have all the appropriate equipment and staff to be able to complete all work. Breckenridge Public Utilities ("BPU") staff will be providing direction and oversight.

BPU will provide all required materials to be buried including the innerduct; however, BPU does not possess an innerduct trailer required to hold and payout innerduct. This trailer(s) will need to be provided by the contractor. Some pulls will require up to 6 ea. of 2" innerduct which could require multiple bores in those locations. The work will tentatively begin around the beginning of May or sooner pending delivery of components and weather; the target completion date is the end of June.

Contractor responsibilities:

- All utility locates
- Complete all required boring (boring depth to target 42" - 48")
- Pulling in the innerduct
- Provide all hardware needed to pull innerduct
- Provide innerduct trailer (needs to be able to handle minimum of 4 ducts)
- Setting basements for the transformers, junction boxes, pedestals and switches (approx. 23)
 - NOTE: BPU personnel to work with contractor on this.

- Cutting and removing concrete or asphalt if needed (should be minimal)
- All bore pit and box (switches, transf., peds, J Boxes) excavations
- Pit restoration with good quality black dirt to level grade with slight crown to allow for settling.

BPU responsibilities:

- Staking of the proposed route
- Provide the innerduct and misc. splicing hardware
- Providing notice to the city residents
- Assist in setting of required basements
- Repair or replacement of any asphalt or concrete that has been removed by contractor
- Seeding excavation areas

Plans may require slight altering, and certain lengths of boring and innerduct may change slightly during the project. Therefore; **all bids for boring are to be based on a “per linear foot bored”**. Additionally, a lump sum bid is required for each basement that is required to be set. (approx. 23)

Example:

Standard cost of \$xx per/ft for boring and pulling first 2 pipes, plus upcharge of \$x for each additional pipe beyond the first two pipes. \$x per basement set.

Each bid must be accompanied by a bid bond payable to the City of Breckenridge, Minnesota, in the amount of five percent (5%) of the total bid. This is to serve as a guarantee that the bidder will enter into a contract for the performance of such work if the contract is awarded to them. Only bids that are accompanied by such bond in the envelope will be considered. The contract awarded to the lowest responsible bidder shall be on the form required by the City. A copy of the required contract form, including insurance along with performance and payment bond requirements, may be requested by bidders from the City Administrator.

Bid opening will take place at 1:00 PM on Friday, Feb 26th, 2021. Sealed Bids will be accepted at City Hall until that time. Sealed Bids can also be mailed to:

**City Hall
420 Nebraska Ave
Breckenridge, MN 56520
Attention: Renae Smith**

The City of Breckenridge reserves the right to reject any and all bids.

Please direct any questions regarding this bid to:

Neil Crocker
Director of Public Services
ncrocker@breckenridgmn.net
701-640-0133 Mobile
218-643-4681 Office

2021 New York Ave. Utility Work for South Side Drainage project									
	C-1	C-2	C-3	C-4	C-5	C-6	C-7	Total bore LF	Total Pipe LF
1 Pipe	210	265	240	210			120	1045	1045
2 Pipes			370				115	485	970
3 Pipes	200	365	230			50	115	960	2880
4 Pipes	250			725				975	3900
5 Pipes			325					325	1625
6 Pipes	65	360				265		690	4140
								Approx. Total linear ft to bore: 4480	
									14560
Approx. total Structures to be set (23)									
Switches		2							
Transformers		8							
Secondary Peds		11							
Junction Boxes		2							